

Phase	Strom (A)	Spannung (mV)	Ri (mOhm)	
A - B	7,59	93,4	12,31	471g
A - C	7,58	92,1	12,15	
C - B	7,58	95,7	12,63	
			12,36	16°C

Katalogangabe

13 mOhm

HKIV-4035-560KV an YGE-205HVT-opto

Zellen	Spannung	Strom	Drehzahl	KV ₀
6	24,97	4,19	13.410	537,0
7	29,18	4,53	15.682	537,4
8	33,31	4,95	17.870	536,5
10	41,66	5,82	22.379	537,2
11	45,78	6,12	24.640	538,2
12	50,00	6,92	26.963	539,3

Phase	Strom (A)	Spannung (mV)	Ri (mOhm)	
A - B	7,57	97,5	12,88	505g
A - C	7,55	96,7	12,81	
C - B	7,57	98,1	12,96	
			12,88	14°C

Katalogangabe

13 mOhm

Lehner TorqStar 4125-18 an YGE-205HVT-opto

Zellen	Spannung	Strom	Drehzahl	KV ₀
6	22,51	2,45	12.923	574,1
7	26,28	2,60	15.082	573,9
8	30,08	2,78	17.284	574,6
10	37,45	3,17	21.545	575,3
11	41,22	3,35	23.794	577,2
12	44,99	3,53	26.008	578,1
13	48,76	3,73	28.227	578,9

PowerDekker HKII-4225-615KV

YGE-205HVT-opto (Auto-T)

Phase	Strom (A)	Spannung (mV)	Ri (mOhm)	Messung PD (mOhm)
A - B	7,59	81,90	10,79	10,4
A - C	7,58	82,50	10,88	
B - C	7,57	81,80	10,81	

405g**10,83** 16°C**PD-4225-614KV mit YGE-205HVT opto - Auto Timing**

Zellen	Spannung	Strom	Drehzahl	KV
6	22,47	2,59	13.758	612,28
7	26,16	3,62	16.005	611,81
8	29,94	3,70	18.349	612,86
10	37,23	4,23	22.814	612,79
11	40,99	4,39	25.147	613,49
12	44,77	4,63	27.478	613,76
13	48,53	4,83	29.829	614,65

PowerDekker HKII-4525-578KV

YGE-205HVT-opto (Auto-T)

Phase	Strom (A)	Spannung (mV)	Ri (mOhm)	Messung PD (mOhm)
A - B	7,58	64,60	8,52	8,1
A - C	7,58	64,10	8,46	
B - C	7,57	64,10	8,47	

514 g**8,48** 16°C**PD HKII-4525-578 mit YGE-205HVT-OPTO - Auto-Timing**

Zellen	Spannung	Strom	Drehzahl	KV
6	22,35	3,76	12.904	577,36
7	26,10	4,34	15.059	576,97
8	29,87	4,73	17.230	576,83
10	37,04	5,67	21.372	577,00
11	40,71	5,87	23.537	578,16
12	44,50	6,09	25.749	578,63
13	48,23	6,35	27.921	578,91